

**REPORT  
 of  
 RECLOSER CONTROLLER SIMULATED SURGE ARRESTER  
 OPERATION TEST**

**SPECIMEN DESCRIPTION**

Recloser Control:	Beckwith Control		
Control Part #	A-7679#29234		
Control Serial #	101 471-1314		
Three-phase Recloser:	G&W Viper-ST Type VIP388ER-12-1 ST		
Impulse level (BIL):	125 kV <sub>peak</sub>		
Rated Voltage:	27 kV <sub>rms</sub>		
Rated Current:	800 A <sub>rms</sub> continuous		
Viper ST Serial No.:	2017 0130 0001		
Reference drawing: D870A PT2I A00	Photographs attached:	Yes: <input checked="" type="checkbox"/>	No: <input type="checkbox"/>

Dates of Test: 13-November-2018 through 14-November-2018

**REQUIREMENTS**

Standard:	C37.60-2012 Section 6.111.3, "Simulated Surge Arrester Operation Test"
-----------	--

Test Voltage and Current: 120 kV<sub>peak</sub> (150 kV<sub>peak</sub> x 0.8), 6 kA<sub>peak</sub> (Note: tested at 38KV level)

**Configurations:**

Condition	Description of Applied Impulses	Point of Application	Switch Position
A	15 surges of (+) polarity and 15 surges of (-) polarity	source bushings	open
B	15 surges of (+) polarity and 15 surges of (-) polarity	source bushings	closed
C	15 surges of (+) polarity and 15 surges of (-) polarity	load bushings	closed
D	15 surges of (+) polarity and 15 surges of (-) polarity	properly rated transformer	open
E	15 surges of (+) polarity and 15 surges of (-) polarity	properly rated transformer	closed

Note: control unit was tested with (42-Pin Cabinet tested with new AC transfer switch, DIP board, original AC/DC converter)

**TEST RESULTS:**

The recloser and controls continued to function after all surges had been applied.

**CONCLUSION:**

The recloser and controls complied with the requirements of IEEE Standard C37.60-2012, Section 6.11.3.

Report Prepared By:	Nader Samara	Date:	16-November-2018
Signed by:	Nick Nakamura	Date:	29-November-2018



**SSAO Recloser test setup**



**SSAO Transformer test setup**



**SSAO Control Setup**





Beckwith control screen display

**REPORT  
of  
RECLOSER CONTROLLER SIMULATED SURGE ARRESTER  
OPERATION TEST**

**SPECIMEN DESCRIPTION**

Recloser Control:	Beckwith Control		
Control Part #	A-7679#29234		
Control Serial #	101 471-1314		
Three-phase Recloser:	G&W Viper-ST Type VIP388ER-12-1 ST		
Impulse level (BIL):	125 kV <sub>peak</sub>		
Rated Voltage:	27 kV <sub>rms</sub>		
Rated Current:	800 A <sub>rms</sub> continuous		
Viper ST Serial No.:	2017 0130 0001		
Reference drawing: D870A PT2I A00	Photographs attached:	Yes: <input checked="" type="checkbox"/>	No: <input type="checkbox"/>

Dates of Test: 14-November-2018 through 15-November-2018

**REQUIREMENTS**

Standard:	C37.60-2012 Section 6.111.3, "Simulated Surge Arrester Operation Test"
-----------	--

 Test Voltage and Current: 120 kV<sub>peak</sub> (150 kV<sub>peak</sub> x 0.8), 6 kA<sub>peak</sub> (Note: tested at 38KV level)

**Configurations:**

Condition	Description of Applied Impulses	Point of Application	Switch Position
A	15 surges of (+) polarity and 15 surges of (-) polarity	source bushings	open
B	15 surges of (+) polarity and 15 surges of (-) polarity	source bushings	closed
C	15 surges of (+) polarity and 15 surges of (-) polarity	load bushings	closed
D	15 surges of (+) polarity and 15 surges of (-) polarity	properly rated transformer	open
E	15 surges of (+) polarity and 15 surges of (-) polarity	properly rated transformer	closed

Note: control unit was tested with (42-Pin Cabinet tested with new AC transfer switch, DIP board replaced with DIP without TVSs (no protection), new AC/DC power supply used)

**TEST RESULTS:**

The recloser and controls continued to function after all surges had been applied.

**CONCLUSION:**

The recloser and controls complied with the requirements of IEEE Standard C37.60-2012, Section 6.11.3.

Report Prepared By:	Nader Samara	Date:	16-November-2018
Signed by:	Nick Nakamura	Date:	29-November-2018




**SSAO Recloser test setup**





**SSAO Transformer test setup**



**SSAO Control Setup**



Beckwith control screen display