



70.0 ± 2.8 @ 1.5 DIA.

ITEM NO	NAME	DESCRIPTION	MATERIAL	PCS/ASSM	COMPONENT NO	FT-PCS/100 ASSM	MAT'L COST/UNIT	LABOR COST/UNIT	MAT'L COST/100 ASSM	LABOR COST/100 ASSM
1	MESH	STRAND	GAU. STL.	—	373-01-010	1				
2	STRAND TAB, Q.W.	TUBE - FLATTENED	CU	6	312-43-028	3				
3	STRAND TAB, T.W.	TUBE - FLATTENED	CU	6	312-43-023	3				
4	END TAB	TUBE - FLATTENED	CU	6	312-43-021	3				
5	INSTRUCTIONS	INSTALLATION	PAPER	1	309-20-103					
6	FASTENER	TIE WRAP	PLASTIC	2	316-20-001					
7	TAG	IDENTIFICATION	MYLAR	1						



kellems division

HARVEY HUBBELL INC.
Route 1, Lord's Hill
Stonington, Conn.

TITLE: GRIP, GAU. STL. - PULLING, REGULAR
WIRE ROPE - CLOSED MESH, MULTI-WEAVE, DOUBLE ENDED
FOR 1/8" OR 1/2" WIRE ROPE
DESCR: 1/8" & 1/2" RWR
APPROX. QTY/STR: 20,000 WRT/100 (LBS)

MFG METHOD	SCALE	ASSEMBLY
STD	1/2" = 1'	TOTAL
DATE: 12/28/79	CHECKED BY	CALCULATED BY
APPROVED BY		

TOLERANCES UNLESS OTHERWISE SPECIFIED
.X ± .5 .XX ± .05 .XXX ± .015
ANGLE'S ± 2°