


4-11/16" Square Box Pre-Fab Assemblies

By Raco Catalog # AW2.1.16

STAB-iT* Pre-Fab Assembly, 9020R model + 252SCM model + 838 model / 1G - Mud Ring, Raised 3/4" / 16" Studs



Features

- · Ready to install, no preparation required
- For use on wood or metal studs
- · Designed and assembled in USA

Application

- Save labor costs on any job with RACO Pre-Fab assemblies. All components come pre-assembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.
- These Assemblies feature 4-11/16" boxes with integrated STAB-iT® II connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4-11/16" box with additional knockouts.

General

Cable Clamps

Drawn or Welded Welded

Knockouts (1) 1/2", (10) 1/2 - 3/4" TKO, (1)

3/4 - 1" TKO

Material Steel
Number of Gang(s) 1-Gang

UPC 050169993293

Wiring System Flex

Dimensions

Cubic Capacity	42
Raised Ground	Yes
Raised Height	0.75 in

Certifications and Compliance

Certified Listed UL Listed

Logistics

Carton Quantity 6
Pallet Quantity 180

Product Assets

Brochures - Product Solutions for Electrical Prefabrication Catalogs - RACO / TayMac / Bell Full Catalog Installation Manuals - EP-RACO-CC-IOM-EN-00353 web Sell Sheets - 4-11/16" STAB-iT II Box Assemblies for Pre-Fab Sell Sheets - RA_448_SEL_PREFAB

