

4-11/16" Square Box Pre-Fab Assemblies

By Raco Catalog # AW2.1.16

STAB-iT® Pre-Fab Assembly, 9020R model + 252SCM model + 838 model / 1G - Mud Ring, Raised 3/4" / 16" Studs



Features

- Ready to install, no preparation required
- For use on wood or metal studs
- · Designed and assembled in USA

General

Application

Save labor costs on any job with RACO Pre-Fab assemblies. All components come preassembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.

These Assemblies feature 4-11/16" boxes with integrated STAB-iT® II connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4-11/16" box with additional

knockouts.

Cable Clamps

Drawn or Welded Welded

Knockouts (1) 1/2", (10) 1/2 - 3/4" TKO, (1)

1

3/4 - 1" TKO

Material Steel
Number of Gang(s) 1-Gang

UPC 050169993293

Wiring System Flex

Dimensions

Cubic Capacity 42
Raised Ground Yes
Raised Height 0.75 in

Certifications And Compliance

Certified Listed UL Listed

Logistics

Carton Quantity 6
Pallet Quantity 180

Product Assets

Brochures - Product Solutions for Electrical Prefabrication Catalogs - RACO / TayMac / Bell Full Catalog

Installation Manuals - Instructions for AW Series 4-11/16" STAP-IT II Box Assemblies

Installation Manuals - EP-RACO-CC-IOM-EN-00353 web

Sell Sheets - RA_448_SEL_PREFAB

Sell Sheets - 4-11/16" STAB-iT II Box Assemblies for Pre-Fab



©2024 Hubbell Incorporated. All rights reserved RACO-AW2116-SPEC-EN | REV 6/2024