

4-11/16" Square Box Pre-Fab Assemblies

By Raco Catalog # AW5.1.16

STAB-iT® Pre-Fab Assembly, 9020R model + 252SCM model + 840 model / 2G - Mud Ring, Raised 3/4" / 16" Studs

Features

- Ready to install, no preparation required
- For use on wood or metal studs
- Designed and assembled in USA

General

Application

with RACO Pre-Fab assemblies. All components come preassembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.

Save labor costs on any job

These Assemblies feature 4-11/16" boxes with integrated STAB-iT® II connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4-11/16" box with additional knockouts.

Cable Clamps Drawn or Welded Knockouts

Material Number of Gang(s) UPC Wiring System

Welded (1) 1/2", (10) 1/2 - 3/4" TKO, (1) 3/4 - 1" TKO Steel 2-Gang 050169993392 Flex

1



Dimensions

Cubic Capacity	42
Raised Ground	Yes
Raised Height	0.75 in

Certifications And Compliance

Certified Listed	UL Listed
Logistics	
Carton Quantity Pallet Quantity	6 180

Product Assets

Brochures - Product Solutions for Electrical Prefabrication Catalogs - RACO / TayMac / Bell Full Catalog Installation Manuals - Instructions for AW Series 4-11/16" STAP-IT II Box Assemblies Installation Manuals - EP-RACO-CC-IOM-EN-00353 web Sell Sheets - RA_448_SEL_PREFAB Sell Sheets - 4-11/16" STAB-IT II Box Assemblies for Pre-Fab



©2024 Hubbell Incorporated. All rights reserved RACO-AW5116-SPEC-EN | REV 6/2024