

# 9020R + 252SCM + 843HAMR /1G Hinged Adjustable Mud Ring/16" Studs

By Raco Catalog # FW2.7.16





#### **Features**

- · Ready to install, no preparation required
- For use on wood or metal studs
- · Designed and assembled in USA
- Includes Hinged Adjustable Mud Rings for increased productivity

## General

Application Save labor costs on any job

with RACO Pre-Fab assemblies. All components come preassembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite

packaging waste.

These Assemblies feature 4" boxes with integrated STAB-iT® connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include Hinged, Adjustable Mud Rings, built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4" box with additional

knockouts.

Cable Clamps 2

Drawn or Welded Welded

Knockouts (7) 1/2", (4) 1/2 - 3/4" TKO

Material Steel

Number of Gang(s) 1-Gang

UPC 050169927991

Wiring System Multiple

## **Dimensions**

Cubic Capacity 30.3 cu.in Raised Ground Yes

Raised Height 1/2 in - 1-3/8 in

### **Certifications And Compliance**

Certified Listed UL Listed

#### Logistics

Carton Quantity 6
Pallet Quantity 180

#### **Product Assets**

Brochures - Product Solutions for Electrical Prefabrication
Catalogs - RACO / TayMac / Bell Full Catalog
Installation Manuals - Installation Instructions for FW Series 4" Sq
Stab-iT® Wall Assemblies
Sell Sheets - 4" STAB-iT Box Assemblies for Pre-Fab

