

9020R + 232SCM + 231 + (2) 773 / 1G - Mud Ring, Raised 3/4" / 24" Studs

By Raco Catalog # FW3.1.24





- · Ready to install, no preparation required
- For use on wood or metal studs
- Designed and assembled in USA

General

Application

Save labor costs on any job with RACO Pre-Fab assemblies. All components come pre-assembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.

These Assemblies feature 4" boxes with integrated STAB-iT® connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4" box with additional knockouts.

Cable Clamps

Drawn or Welded Welded

Knockouts (7) 1/2", (4) 1/2 - 3/4" TKO

MaterialSteelNumber of Gang(s)1-GangUPC050169927861Wiring SystemMultiple



Dimensions

Cubic Capacity 30.3 cu.in Raised Ground Yes

Certifications And Compliance

Certified Listed UL Listed

Logistics

Carton Quantity 6 Pallet Quantity 144

Product Assets

Brochures - Product Solutions for Electrical Prefabrication Catalogs - RACO / TayMac / Bell Full Catalog Installation Manuals - Installation Instructions for FW Series 4" Sq Stab-iT® Wall Assemblies

Sell Sheets - 4" STAB-iT Box Assemblies for Pre-Fab



©2024 Hubbell Incorporated. All rights reserved RACO-FW3124-SPEC-EN | REV 6/2024