



232MSCM + 779 / 2G - Mud Ring, Raised 3/4" / M Bracket

By Raco
Catalog # FW4.1



232MSCM + 779 / 2G - Mud Ring, Raised 3/4" / M Bracket

Features

- Ready to install, no preparation required
- For use on wood or metal studs
- Designed and assembled in USA

Application

- Save labor costs on any job with RACO Pre-Fab assemblies. All components come pre-assembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.
- These Assemblies feature 4" boxes with integrated STAB-iT® connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4" box with additional knockouts.

General

Cable Clamps	2
Drawn or Welded	Welded
Knockouts	(7) 1/2", (4) 1/2 - 3/4" TKO
Material	Steel
Number of Gang(s)	2-Gang
UPC	050169927892
Wiring System	Multiple

Dimensions

Cubic Capacity	30.3 cu.in
Raised Ground	Yes

Certifications and Compliance

Certified Listed	UL Listed
------------------	-----------

Logistics

Carton Quantity	12
Pallet Quantity	576

Product Assets

[Brochures - Product Solutions for Electrical Prefabrication](#)
[Catalogs - RACO / TayMac / Bell Full Catalog](#)
[Installation Manuals - Installation Instructions for FW Series 4" Sq Stab-iT® Wall Assemblies](#)
[Sell Sheets - 4" STAB-iT Box Assemblies for Pre-Fab](#)



A proud member of the Hubbell Family.

©2024 Hubbell Incorporated. All rights reserved.
RACO-FW4.1-SPEC-EN | REV 1/2024