


9020R + (232SCM + 779) / 2G -Adj. Mud Ring, Raised 3/4" + (231 + 773) / 1G Adj. Mud Ring / 16" Studs

By Raco Catalog # FW6.1.16





- · Ready to install, no preparation required
- For use on wood or metal studs
- Designed and assembled in USA

Application

- Save labor costs on any job with RACO Pre-Fab assemblies. All components come pre-assembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.
- These Assemblies feature 4" boxes with integrated STABiT* connectors for advanced fast, secure installation of MC
 cables. Contractor-proven to install MC in just 1/3 the time!
 These boxes also include built-in cable management clip
 and 8" solid #12 pigtail. Models with a second box for
 power and data applications include a standard 4" box with
 additional knockouts.



General

Cable Clamps 2

Drawn or Welded Welded

Knockouts (7) 1/2", (4) 1/2 - 3/4" TKO

Material Steel
Number of Gang(s) 2-Gang

UPC 050169927946

Wiring System Multiple

Dimensions

Cubic Capacity 30.3 cu.in Raised Ground Yes

Certifications And Compliance

Certified Listed UL Listed

Logistics

Carton Quantity 6
Pallet Quantity 240

Product Assets

Brochures - Product Solutions for Electrical Prefabrication Catalogs - RACO / TayMac / Bell Full Catalog Installation Manuals - Installation Instructions for FW Series 4" Sq Stab-iT* Wall Assemblies

Sell Sheets - 4" STAB-iT Box Assemblies for Pre-Fab

