



4-11/16" Square Box Pre-Fab Assemblies

By Raco
Catalog # [AW2.9.24](#)



STAB-iT® Pre-Fab Assembly, 9020R model + 252SCM model + 868AMR model / 1G - Adjustable Mud Ring / 24" Studs

Features

- Ready to install, no preparation required
- For use on wood or metal studs
- Designed and assembled in USA

Application

- Save labor costs on any job with RACO Pre-Fab assemblies. All components come pre-assembled, ready to install right out of the box. Electrical boxes, mounting brackets, cable management and mud rings. Ensure quality while reducing material and labor costs. Even reduce jobsite packaging waste.
- These Assemblies feature 4-11/16" boxes with integrated STAB-iT® II connectors for advanced fast, secure installation of MC cables. Contractor-proven to install MC in just 1/3 the time! These boxes also include built-in cable management clip and 8" solid #12 pigtail. Models with a second box for power and data applications include a standard 4-11/16" box with additional knockouts.

General

Cable Clamps	1
Drawn or Welded	Welded
Knockouts	(1) 1/2", (10) 1/2 - 3/4" TKO, (1) 3/4 - 1" TKO
Material	Steel
Number of Gang(s)	1-Gang
UPC	050169993323
Wiring System	Flex

Dimensions

Cubic Capacity	42
Raised Ground	Yes

Certifications and Compliance

Certified Listed	UL Listed
------------------	-----------

Logistics

Carton Quantity	6
Pallet Quantity	108

Product Assets

[Brochures - Product Solutions for Electrical Prefabrication](#)
[Installation Manuals - EP-RACO-CC-IOM-EN-00353 web](#)
[Sell Sheets - RA_448_SEL_PREFAB](#)



A proud member of the Hubbell Family.

©2023 Hubbell Incorporated. All rights reserved.
RACO_AW2.9.24_SPEC | REV 3/2023